

## **SOW for Shatter Resistant Window Film (SRWF)**

The U.S. Department of State has approved the following SRWF from these companies (in no particular order):

- a. 3M – Ultra 600 (clear)
- b. Bekaert Specialty Films, Inc. – AG PS HC (clear)
- c. Madico, Inc. – LCL-800-XSR (clear)
- d. GlassLock – CP Films SCL SR PS7 (clear)
- e. CPFilms, Inc. – Llummar SCL SR PS7 (clear)

The SRWF must be 8-MIL or performance equivalent. The vendor must clean the windows and/or glass prior to film installation. SRWF will be placed on all glass windows/doors throughout the entire residence (single-family home, townhome, apartment, etc.).

The application of the security film must, at a minimum, cover the clear area of the window. The clear area is defined as the portion of the glass unobstructed by the frame. The film should include less than a 1/8 of an inch (3.175mm) gap on all sides around the clear area to the frame to allow for some “play”.

If the SRWF is not placed properly, then it must be removed and reinstalled by the contractor at no additional charge to the U.S. Government.

The contractor/vendor must maintain on its site (facility/warehouse) enough supplies/stock for an average installation for 10 USG properties.

### **1. GENERAL INSTRUCTIONS:**

- 1.1 All work for this project will occur on Tri-Mission owned or leased housing. The contractor must visit the site in order to verify the requirements prior to the project start date.
- 1.2 The Contractor shall prepare a detailed quotation of the upgrades they plan to complete and the cost of the materials and labor to conclude the project. The Contractor shall provide the quotation (in English) to the Contracting Officer's Technical Representative (RSO) for review as soon as the Task Order has been issued. The Contracting Officer's Technical Representative (RSO) must approve these general instructions before the work is performed.
- 1.3 The Contractor shall complete all work and provide labor and materials required for all the named security upgrades. The price offered shall include all labor, materials, overhead (including cost of Workers' Compensation and Liability Insurance, which shall not be a direct reimbursement), and profit.
- 1.4 All prices are in USD\$ currency and the U.S. Government will make payment in local currency.
- 1.5 The Contractor must provide names of all of the employees who will be working

within this SOW, including replacements, two weeks in advance to the beginning of the project. They will provide a copy of their certificates of conduct from the commune in which they reside. Those personnel must pass an Embassy security check and if they do not, they will need to be replaced by the Contractor with cleared personnel.

## **2. EXECUTION:**

### **2.1 REQUIREMENTS**

The quality of maintenance and appearance of the grass, shrubbery, garden areas, trees, walkways and related landscape elements is important to the U.S. Mission. Any removal or destruction of grass, shrubbery, garden areas, walkways, etc. will need to be refurbished prior to the end of the project by the Contractor at the Contractor's cost.

The requirements include, providing all labor materials such as: uniforms, footwear, rain gear, personal protective equipment. Contractors shall provide equipment, tools, and services required to provide professional construction, replacement and installation of materials included under "specific details". Construction materials (doors, windows, grills, etc.) must be inspected by the designated embassy employee before installation.

In general, the work includes all items listed under "specific details" but is not limited to these items.